

### INSTALLATION GUIDE TRITON<sup>®</sup> BACKER BOARD

### Wall Installation (1/2")

### W1. ENSURE FRAMING IS STRUCTURALLY SOUND AND PROPERLY ALIGNED

- → Wall must comply with local building code and ANSI A108.11
- → Use minimum 2"x4" wood studs or 20 gauge metal studs at maximum 16" o.c.

#### **W2. DETERMINE LAYOUT**

- → TRITON<sup>®</sup> Backer Board edges parallel to framing must be structurally supported
- → Cut backer to size and make necessary cutouts
- → Do not allow four corner joints

### **W3. ATTACH BACKER TO FRAMING MEMBERS**

- → Use proper nails or screws at maximum 8" o.c.
- → Keep fasteners 3/8" from TRITON Backer Board edges and 2" from corners
- → Attach backer to structural members, maintaining 1/8" gap between sheets (to be filled with mortar), and 1/4" gap between backer and floor/tub/shower pan (to be caulked appropriately).
- → Set fasteners flush with TRITON Backer Board

#### **W4. TAPE JOINTS PRIOR TO TILING**

- → Clean seams with damp sponge
- → For in-plane seams, fill seams with mortar and embed 2" wide, high strength, alkali resistant fiberglass mesh tape.
- → For change of plane (corner) joints, space TRITON Backer as required, tape joints using a skim coat of mortar, but do not fill.
- → MiTek Waterproof Seam Tape may also be used over seams



### 5. TO FINISH TRITON BACKER BOARD WITH WALL OR FLOOR TILE

- → Wet area applications require use of the MiTek Watertight System
- → Refer to mortar and tile manufacturers' application guidelines
- → Wipe the surface of the backer with a damp sponge just prior to applying mortar to clean as well as dampen the backer
- → TIP: TRITON Backer Board can be installed with either the smooth or textured side facing out.



### **PROPER FASTENERS:**

Corrosion Resistant Roofing Nails or Cement Backer Screws Min. 1 ¼" for Floors and Interior Walls Min. 1 ¾" for Exterior Walls

# MiTek<sup>®</sup>

800-325-8075



### Floor Installation (1/4")

### F1. ENSURE SUBFLOOR IS STRUCTURALLY SOUND

- → Replace any loose, warped, uneven, or damaged sections
- → Ensure subfloor is clean and flat
- → Structural subfloor must be engineered not to exceed the L/360 deflection criteria or L/720 for natural stone
- → Floor must comply with local building code and ANSI A108.11

### **F2. DETERMINE LAYOUT**

- → Do not align TRITON Backer Board with subfloor joints
- → Do not allow four corner joints
- → Cut TRITON Backer Board to size, make needed cutouts and holes

### **F3. ATTACH BACKER TO SUBFLOOR**

- → Apply supporting bed of mortar that meets or exceeds ANSI A118.1 to subfloor using a 1/4" square notch trowel. For proper guidance regarding specific substrates, refer to mortar manufacturer's guidelines
- → Embed TRITON Backer Board into wet mortar, maintaining 1/8" gap between sheets (to be filled with mortar), and 1/4" gap between backer and walls/cabinet bases/tubs/shower pans
- → Fasten TRITON Backer Board with proper nails or screws every 8" in the field keeping 3/8" from the edge and 2" from the corners

### F4. TAPE JOINTS PRIOR TO TILING

- → Clean seams with damp sponge
- → Fill joints with mortar
- → Embed 2" wide, high strength, alkali-resistant glass fiber tape into the mortar



# 5. TO FINISH TRITON BACKER BOARD WITH WALL OR FLOOR TILE

- → Wet area applications require use of the MiTek Watertight System
- → Refer to mortar and tile manufacturers' application guidelines
- → Wipe the surface of the backer with a damp sponge just prior to applying mortar to clean as well as dampen the backer
- → **TIP:** TRITON Backer Board can be installed with either the smooth or textured side facing out.



### **PROPER FASTENERS:**

Corrosion Resistant Roofing Nails or Cement Backer Screws Min. 1 ¼" for Floors and Interior Walls Min. 1 ¾" for Exterior Walls

# MiTek<sup>®</sup>